NOTICE INVITING QUOTATION (NIQ)

MITL/SBIA/Electrical/NIQ for NSC/644
Date:12.11.2026

Subject: Supply, Installation, Testing, and Commissioning of LT Feeder Pillar along with LT 1.1 KV 3.5Cx300 Sqmm Aluminium Armoured Cable for Providing power supply to M/s Aditya Rudra Industries, Plot No-19, Sector-13 At Auric Bidkin Industrial Area.

Sir,

Maharashtra Industrial Township Limited (MITL) invites sealed quotations for Supply, Installation, Testing, and Commissioning of LT Feeder Pillar along with LT 1.1 KV 3.5Cx300 Sqmm Aluminium Armoured Cable for Providing power supply to M/s Aditya Rudra Industries, Plot No-19, Sector-13 At Auric Bidkin Industrial Area.

Sr No	**Material Sescription**	**Unit**	**Qty**	**Rate**		**Amount**
				Supply	**Errection**	
1	Supplying, erecting & terminating FR XLPE insulated, galvanised steel formed wire armoured **(round)** cable, 1100 V 3½ core 300 sq. mm. aluminium conductor complete erected with glands & lugs on wall/ trusses/pole or laid in provided trench/ pipe as per specification (CSS to Feeder Piller)	M	170			
2	Supplying and erecting mini feeder pillar with 415V, 315-320A FPMCCB as incomer and 3 outgoing circuits with HRC fuse base and cartridge of 100A aluminium bus bar erected in 14 SWG CRCA sheet box with supporting angles, self-locks, gasket and enclosure must be dust proof, rust proof, vermin and water resistant, having slanting top and erected on angle iron/ GI frame in provided C.C. foundation complete as per specification	Each	1			
3	Supplying, installing and testing pipe type earthing with 40mm. dia. G.l. pipe or 20 mm dia. G.I. Rod complete with all accessories of GI materials & recording the results as per specification	Each	2			
4	Making cement concrete foundation in 1:3:6 cement concrete, (20 to 25) mm. stone metal duly plastered with necessary curing for complete.	Cu.m	1			
Total Excluding Taxes						
	Taxes @ 18%					
	Total Estimated Cost including Taxes					

Rates shall be quoted inclusive of all applicable charges (Charging permission, transportation, loading/unloading, etc.)

Total estimated cost of the work is Rs.4,55,441.65 Including Taxes.

The contractor has to pay 5% of security deposit in the form of DD/BG on award of work order.

The is to be executed as per general terms of contract and technical specification as guided/Directed by MITL Authorities.

Pre-qualification: The contractor shall have executed similar type of work amounting not less than Rs. 5 Lakh in last financial year. Submission of experience certificate is necessary.

Completion Period: The work shall be completed within 15 (Fifteen) days from the date of receipt of the Work Order.

Sealed quotations are hereby invited from eligible and experienced Electrical contractors for Supply, Installation, Testing, and Commissioning of LT Feeder Pillar along with LT 1.1 KV 3.5Cx300 Sqmm Aluminium Armoured Cable for Providing power supply to M/s Aditya Rudra Industries, Plot No-19, Sector-13 At Auric Bidkin Industrial Area.

It is requested to submit your quotation on the firm letter head within seven working days i.e. before 20/11/2026 at 15:00 Hrs on following address, soft copy of the quotation shall also be submitted via email to the address mentioned below.

General Manager Electrical (Projects)
Maharashtra Industrial Township Limited (MITL)
Auric Hall Building, Shendra Industrial Area,
Chhatrapati Sambhaji Nagar, Maharashtra 431001
Contact No. +91-7350767131 Email: taeleciandt@mitl.org.in

MAHARASHTRA INDUSTRIAL TOWNSHIP LTD. AURIC CHH.SAMBHAJINAGAR

G.M. (Electrical Projects),
MITL